BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40882

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/29/2019-20, Date: 17.03.2020

Name of Work:Package 03 includes 1 works of Rs. 85.00 lakhs 1)Improvements to drains roads in Maruthi farm in Amruthanagar A Sector in ward no. 7 Byatarayanapura. Est cost Rs.85.00 lakhs.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
1	800.3	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	144.68	Rupees One Hundred Forty Four and Sixty Eight Paise Only
2	110.25	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two and Forty Five Paise Only
3	1451.25	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cm thick all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	779.03	Rupees Seven Hundred Seventy Nine and Three Paise Only
4	187.8	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	902.56	Rupees Nine Hundred Two and Fifty Six Paise Only
5	1035	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	1014.96	Rupees One Thousand Fourteen and Ninety Six Paise Only
6	1236	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	998.27	Rupees Nine Hundred Ninety Eight and Twenty Seven Paise Only
7	4045	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	490.79	Rupees Four Hundred Ninety and Seventy Nine Paise Only
8	1820	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	41.18	Rupees Forty One and Eighteen Paise Only
9	370	Providing and fixing MS Grating 260x260 mm all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	88.98	Rupees Eighty Eight and Ninety Eight Paise Only

Signature of the contractor

19/08

Executive Engineer

19/08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Ra... U RAMESH ( )	
				In Figures	In Words
10	800.3	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	99.05	Rupees Ninety Nine and Five Paise Only
11	135	Laying Reinforced cement concrete pipe NP3 for culverts inlcduding ends and fixing collars with cement mortar 1:2 including cost of materisla, labour, curing including cost of materials, labour HOM complete as per specifications. B. 750 mm dia all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Mtr	3859.52	Rupees Three Thousand Eight Hundred Fifty Nine and Fifty Two Paise Only
12	15.2	Providing 100mm and down size nominal size. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1036.9	Rupees One Thousand Thirty Six and Ninety Paise Only
13	5.09	Providing 40mm and down size nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1145.89	Rupees One Thousand One Hundred Forty Five and Eighty Nine Paise Only
14	5.09	Providing 20mm and down size nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1145.89	Rupees One Thousand One Hundred Forty Five and Eighty Nine Paise Only
15	3.82	Providing Fine aggrgate 2.36mm nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1106.9	Rupees One Thousand One Hundred Six and
16	90	Providing and fixing MS Grating 260x260 mm all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	88.98	Rupees Eighty Eight and Ninety Eight Paise Only
17	45	Direction and place identification signs upto 0.9 sqm size Board - Providing and erecting direction and place identification retro-reflectorised signs as per revised IRC : 67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2mm thick with area not exceeding 0.9 sqm supported on a mild steel single angle iron post 75x75x6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete	Nos	7637.79	Rupees Seven Thousand Six Hundred Thirty Seven and Seventy Nine Paise Only
18	381.5	Providing and applying readymix priming coat concrete / masonry / asbestos cement sheet /plasterd surface including preparing the surface after throughly cleaning of oil grease dirt and other foreign matter and sand papering cost of materials labour as per specifications all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	41.18	Rupees Forty One and Eighteen Paise Only
19	4712.5	Supply MS. Pipe. 25mm dia & 25mm thick all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Mtr	88.98	Rupees Eighty Eight and Ninety Eight Paise Only
20	501.5	Painting on Steel surface :- Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.complete as per specifications MORTH Specification No 803 all leads and lift etc	Sqm	80.13	Rupees Eighty and Thirteen Paise Only
21	78750	Painting new latter and figures any shade with synthetic enamel paint black or any approvel colour to give an even shede complete as per specification (I) Hindi (Matras commas and the like not to be measured and paid for half latter shall be counted as half) all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	cms	1.11	Rupees One and Eleven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
19/08